




Date		Type	P857RA — SPACE LABS
12 PIN		2 LES LED	

LED




red. yellow






white black


I.R.



Red



Sensor



Drawn By:	Signed
-----------	--------

20/7/00

P 858 TO P 857

~~1/ CUT OFF~~

1/ CUT OFF ORANGE, BOTH SHIELDS TOGETHER.
(BLACK STRAIN RELIEF, CABLE CLAMP)

1/ WHITE
(ON SHORT LEE'S RESISTOR)

2/ BLACK & 10R (RESISTOR)

3/ BOTH SHIELDS & ALL 3 RESISTORS


4/ N/C

5/ N/C

6/ N/C

7/ 62K RESISTOR

8/ 7K5 RESISTOR




9/ N/C

10/ N/C

11/ RED


12/ YELLOW



(7 PINS) GREY PLUS

5/6/00 ~~857~~ 47

- 1. take lines out of shield.
- 2. take orange off. tin rest.
- 3. heatshrink connector. shields together. Pins on end. leave Black.



- 1. white
- 2. Black
- 3. shield
- 4. N/C
- 5. N/C
- 6. N/C
- 7. 50K
- 8. 50K
- 9. N/C
- 10. N/C
- 11. Red
- 12. Yellow